

# प्रतिभूति कागज कारखाना, नर्मदापुरम-461005 ( म.प्र. )

( भारत प्रतिभूति मुद्रण तथा मुद्रा निर्माण निगम लिमिटेड की डकार्ड ) भारत सरकार के पूर्ण स्वामित्वाधीन





## SECURITY PAPER MILL, NARMADAPURAM - 461005 (M.P.)

(A Unit of Security Printing & Minting Corporation of India limited) Wholly Owned by Government of India

Miniratna Category - I CPSE & ISO 9001: 2015, 14001:2015, 45001:2018, 50001:2018 & IEC 17025:2017 Certified

CIN: U22213DL2006GOI144763, GSTIN: 23AAJCS6111J3ZE

Tel. No. 07574-255259, Fax No.: 07574-255170, E-mail: gm.spm@spmcil.com, Website: http://spmnarmadapuram.spmcil.com

### शुद्धि पत्र / CORRIGENDUM - I

क्रमांक : 6000017720/Civil/ 1225

दिनॉक: 03.10.2022

संदर्भ : पूछताछ क्रमांक 6000017720/Civil/Hydrant/706 दिनॉक : 29.08.2022

Ref.: Our Tender Enquiry No. 6000017720/Civil/Hydrant/706 Date: 29.08.2022

संदर्भित निविदा सूचना दिनॉक 30.08.2022 http://spmnarmadapuram.spmcil.com पर प्रकाशित की गई थी, जिसके संदर्भ में निम्नान्सार संशोधन करते हुए शुद्धि पत्र -1 जारी किया जा रहा है ।

Against our above tender enquiry was published in the http://spmnarmadapuram.spmcil.com on dated 30.08.2022. Further, to this Corrigendum-I as below is being issued to the tender enquiry with the following amendments:

Sr. no.	Description	For	Read as			
1.	Section XI:	Sr. No. 7 of Price Schedule – 6 EA	Sr. No. 7 of Price Schedule – 25 EA			
=	Price Schedule Point no. 2	Sr. No. 8 of Price Schedule – 15 CUM	Sr. No. 8 of Price Schedule – 6 CUM			
2.	Section I: Notice Inviting Tender	Date of sale of tender documents: From 29.08.2022 to 04.10.2022 during office hours.	Date of sale of tender documents: From 29.08.2022 to 14.10.2022 during office hours.			
		Closing Date and time for receipt of tenders - 04.10.2022 (15:00 hrs)	Closing Date and time for receipt of tenders - 14.10.2022 (15:00 hrs)			
		Opening date and time of tenders: 04.10.2022 (15:00 hrs)	Opening date and time of tenders: 14.10.2022 (15:00 hrs)			

निविदा सूचना की अन्य सभी शर्तें यथावत रहेंगी।

All other terms & condition of tender enquiry shall remain unaltered.

प्रबंधक (सामग्री) / Manager (Material) 03 राजभ्य

हेतु – मुख्य महाप्रबंधक / For- Dhief General Manager



ANNEXURE-I

#### Section XI: Price Schedule

#### TENDER NO. 6000017720/CIVIL/706 Dt. 26.08.2022

The Price bid should clearly indicate the break-up of the price as under:GSTIN No. of your Firm:

Sr.	Description	HSN	Qty	Unit	Rate	Amount
No.						
1	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m:  Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia		110	Mtr		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level.  1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)		7	Cum		
3.	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:  1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size de rived from natural sources)		9	Cum		
4.	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of		110	Sqm		



	columns, etc. for mass concrete				
5.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars of grade Fe-500D or more.	\$ 990	KG		
6.	. Providing and laying Double Flanged (screwed / welded) centrifugally (Spun) Cast Iron, Class B (IS: 1536) including Cl standard specials such as tees, bends, collars, tapers, caps etc., suitable for flanged jointing as per IS: 1538: 150 mm dia C.I. Double Flanged Pipe	650	Mtr		18
7.	Providing and fixing Fire Hydrant stand post shall consist one sluice valves complete with bolts, nuts rubber insertion etc, road surface box, a duck foot bend, flange riser and a stand post column fitted with male coupling confirming to all requirement as mentioned in IS 908	25	EA		
8.	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - incharge.	6	Cum		
9.	. Earth work in surface excavation not exceeding 30 cm in depth including consolidating by ramming and watering, getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:  Qty:-60 Sqm	60	Sqm		
10	Total				
11	Any other charges (if any)				
12	Total				



13	Total GST amount			
14	Total			
15	Total Price (F.O.R, SPM, HOSHANGABAD) (in figures only) (46+47)			
16	Total Price (F.O.R, SPM, HOSHANGABAD) (in words only)			

Note:-The method of evaluation of L1 criteria for awarding the contract shall be decided taking into consideration the total landed price up to SPM Narmadapuram.

Signature	 	
Name	 	
Designation	 	
Date		