

Event Catalogue

Select Financial Year:

2022-2023 ▼

Search Event:

86

Search

Select Event No.:

SPMCIL/Currency Note Press Nashik/Purchase/13/22-23/ET/86[Job Work of EPU Flooring] ▼

Event Details

Event No: SPMCIL/Currency Note Press Nashik/Purchase/13/22-23/ET/86[Job Work of EPU Flooring]				Event Status
Trade: Works				Event Activated
Description of Event: Job Work of EPU Flooring				Activities
Mode: E-Tender_HTML	Type of Tender: Open	Bid Submission: Eventwise	Public Opening: YES	Published on: 2022-06-15-08.58.20.341946 Activated on: 2022-06-15-10.53.08.725289
EMD: 701000.00 (In Rs.) Bank Details	Document Upload: YES		Tender Extended on: -	
Tender Fee: Not Applicable (In Rs.) Bank Details	Coverwise Document Upload: YES		Tender Opened on: -	
Estimated Value: 35010600.00			Price Opened on: - Event Cancelled on: -	
Online Pre Bid Meeting	Bidding Period	Tender Opening Period	Price Bid Opening Date	
Not Applicable	15.06.2022 - 11:00 AM To 15.07.2022 - 11:00 AM	15.07.2022 - 11:01 AM To 15.07.2023 - 11:01 AM	-	

List Of Tender Document

Sl. No.	Document Details	Document Type	Action
1	22-23-ET-86[Job Work of EPU Flooring]-167224-NIT-1124081-EPUFLOORINGTENDER.pdf 15/06/2022 08:57:53	NIT	Download

Vendor Document Upload Checklist For Technical COVER

Sl. No.	Document Details
1	All the required documents as per Section IX Eligibility Criteria of Tender Documents
2	Duly sealed and signed as per instructions provided in the various sections.

Vendor Document Upload Checklist For Price COVER

Sl. No.	Document Details
1	Bidder has to submit duly filled price schedule in the format as per Section XI of Tender Documents

Tender Committee Members						
Name	Designation	Office	Department	Email	Mobile No.	Encrypt public expi data
VUPPALA KIRAN KUMAR	Jt. General Manager	Currency Note Press Nashik	Purchase,HR,Technical,Finanace,IT,Marketing,R and D,Others	V.Kirankumar@spmcil.com	9096000418	2022-00:00:
TUSHARKUMAR PRAKASH MAHAJAN	DGM	Currency Note Press Nashik	IT	tushar.mahajan@spmcil.com	8275022966	2022-00:00:
BHARATI DHIRENDER SHARMA	MANAGER	Currency Note Press Nashik	Finanace	bharati.sharma@spmcil.com	8888635230	2022-00:00:

Lot No : 1						
Lot Name	Category	Lot Description	Quantity/UOM	Currency	Ceiling Price	Estimated Price
Job Work of EPU Flooring	Civil Works	Job Work of EPU Flooring	1.0 Activity	INR	-	-

Lot No: 1 Specific Terms		
ELIGIBILITY CRITERIA		
Sl.No	Terms	Component
1	Experience and past performance: The bidder should have experience of having successfully completed similar works during last 7 years ending on 31.03.2021. a. Three similar completed works each costing not less than the amount equal to Rs. 1,40,04,240- or b. Two similar completed works each costing not less than the amount equal to Rs. 1,75,05,300- or c. One similar completed work costing not less than the amount equal to Rs. 2,80,08,480-.	Agree Only
2	Capacity and Capability Criteria: The bidder should be enlisted in either Central Public Works Department (CPWD) or Military Engineering Services (MES) or any other Government / PSU / Autonomous bodies.	Agree Only
3	Financial Standing: (a) Average Annual Turnover of the Bidder firm during last three years ending March 2021 should be more than Rs. 1,40,04,240- (b) Bidder firm should not have suffered any financial loss for more than one year during the last three financial years ending March 2021. (c) The net worth of the firm should not be negative and should not have eroded by more than 30% in the last three financial years ending March 2021.	Agree Only
4	The bidder should give a declaration that they have not been black-listed/debarred for dealing by Government of India in the past.	Agree Only
5	The bidder should submit Power of Attorney of the Authorized Signatory for signing the bid, entering in to contract, if awarded and for any other correspondences.	Agree Only
6	The bidders shall enclose attested copy of GST Registration Certificate (in Reg-06 Format) & attested PAN Card Copy.	Agree Only
7	The bidder should give undertaking/declaration that they have read and understood all the terms & conditions of tender documents and submitting unconditional acceptance to all terms & conditions.	Agree Only

TECHNICAL SPECIFICATIONS		
Sl.No	Terms	Component

1	<p>1. Dismantling of 40 mm thick bitumen mastic wearing course by mechanical manual means including disposal of the dismantled material up to a lead of 3 Km. The quoted rate shall include cost of all labour, equipment, hire charges for vehicle, tools tackles etc. Estimated Qty. 1300.00 m²</p> <p>2. Dismantling of existing 3mm thick PVC flooring including removing the layers of Adhesive and cleaning the floor. The scope of work shall also include disposal of the PVC flooring in CNP-IV scrap yard up to a distance of 1.50 Km. The quoted rate shall include cost of all labour, hire charges of vehicle for disposal, tools tackles etc. Estimated Qty. 6500.00 m²</p> <p>3. Dismantling of concrete floor of grade up to M-20 shahbad stone flooring of thickness up to 4 inches to bring the pot holes in to proper shape for filling epoxy screed. The scope of work shall also include disposal of debris to a designated place up to a distance of 3 Km. The quoted rate shall include cost of all labour, equipment, tools tackles, hire charges for vehicle for disposal etc. Estimated Qty. 950.00 m²</p> <p>4. Providing and applying self-leveling EPU flooring system with the following scope of work: a Preparing the surface by mechanical scarification, grinding with mechanical grinders, removing of dust particles, oil, grease and cleaning of grinded floor with broom and vacuum cleaner to provide proper key of the EPU coating to the floor. b Filling up gap cracks if any to the floor where EPU flooring is proposed and level the floor with epoxy mortar wherever required including epoxy primer. c Applying low viscous epoxy primer to a thickness of 100-200 microns with resins and hardner in 1:1 ratio by volume using stiff brush, roller or leveller on dry prepared surface. The primer should be tack free before application of screed coat. Allow the primer to dry to minimum 8 to 12 hours before laying of the screed. d Applying solvent free self-leveling smoothing screed base 4 mm average thickness. The screed coat shall consist of resin, hardner, EPI Pigment as per final coat and formulated aggregates Fq. Sand 200. The screed shall be applied by notch trowel and mixing shall be done with an electric variable mixer thoroughly till obtaining homogenous mixture. The spiking shall be followed with spike roller in weight coating to remove entrapped air. The screed coat shall be allowed to cure for 12 Hours. e Laying of self-smoothing floor top coat of 2 mm thickness. The material shall consist of resin, hardner, formulated aggregates and EPI Pigment Color shade in the pre-weighed kit. The color shade shall be approved by CNP. The quoted rate shall include cost of all materials, labour, transportation, equipments, tools tackles etc. Approved Make: Cipy Fosroc Chemicals Krayon Corporation Estimated Qty. 10000.00 m²</p>	Agree Only
2	<p>5. Providing and applying wall to floor Epoxy coving of size 70 mm x 70 mm with the following scope of work: (a) Preparing the surface by mechanical scarification, vacuum cleaning, grinding, removing of dust particles, oil, grease if any to provide proper key to Epoxy coving. (b) Applying primer coat. (c) Applying 3" coving by mixing silica sand and epoxy primer. (d) Applying epoxy primer on dried coving. (e) Applying putty on coving. (f) Applying two coats of PU paint. The color shade shall be approved by CNP. The quoted rate shall include cost of all materials, labour, transportation, equipment, tools & tackles etc. Estimated Qty. 2500.00 m</p> <p>6. Applying aromatic PU coating of approved shade for markings of width 75 mm and 1 mm thickness. The PU coat shall consist of resin and hardner in 1:1 ratio and shall be mixed with sitrer. The PU coating shall be done with roller. The quoted rate shall include cost of all materials, labour, transportation, sundries, tools & tackles etc. Estimated Qty. 3500.00 m</p> <p>7. Filling of pot holes of depth up to 4 inches with Epoxy screed to make the area in line and level with the adjoining floor surface. The quoted rate shall include cost of all materials, labour, transportation, tools & tackles, equipment etc. Estimated Qty. 1000.00 m²</p> <p>8. Raising manhole cover and frame slab for rectangular chambers of size 720 mm x 720 mm for a height up to 250 mm including dismantling existing slab and adjoining floor area and making good the damage. The quoted rate shall include cost of all materials, labour, transportation, tools & tackles etc. (Cost of chamber cover and frame shall be paid separately) Estimated Qty. 30.00 EA</p> <p>9. Providing and fixing Cast iron rectangular cover of size 690 mm x 690 mm light duty without frame for manhole chambers. The quoted rate shall include cost of all materials, labour, transportation, tools & tackles etc. Estimated Qty. 30.00 EA</p> <p>10. Providing and fixing Cast iron rectangular frame of size 720 mm x 720 mm light duty for manhole chambers. The quoted rate shall include cost of all materials, labour, transportation, tools & tackles etc. Estimated Qty. 30.00 EA</p>	Agree Only

TERMS AND CONDITIONS

Sl.No	Terms	Component
1	<p>1. The firm shall arrange for all the materials, consumables, labour, equipment, vehicles, tools tackles as per the requirement. 2. The area taken for EPU flooring is printing and processing sections and therefore, these sections cant be spared at once. These sections shall be taken for EPU flooring as per the convenience of the section concerned without hampering the production. 3. The firm shall, at no extra cost, cover all the machines and equipment present in the section with tarpaulin and shall also curtain the work area so as to avoid dust to enter in the machine area. 4. The firm shall take necessary safety precautions while carrying out the work. Total responsibility of Contractor persons will lie on the contractor not on C.N.P. 5. The firm shall provide PPE to their workmen while working at site. 6. Firm shall clean the site before handing over to C.N.P. 7. The firm shall dispose all the debris generated during the work to the designated place within a distance of 2 Km. 8. The firm shall arrange for the vehicle for disposing the debris generated and vehicle must have all necessary statutory requirements completed valid drivers license. 9. The working time shall be 8.00 am to 5.00 pm including lunch hour. 10. Electricity required will be provided by C.N.P. at site but the Responsibility of safe use of electricity will be on contractor not on C.N.P. 11. The firm shall take extra care while executing the work as the sections considered for EPU flooring are having printing machines and those machines must be covered properly including provision of curtain for separation of work area and other machine area.</p>	Agree Only

Price Parameters/ Formula

Variable Name	Name of Parameters	Sub Total Example: a+b	Type of Component	Places of decimal	Lumpsum
a	TOTAL AMOUNT OF JOB WORK OF EPU FLOORING INCLUDING GST	-	Numeric Text Only	2	No
<p>Price formula</p> <p>a (Up to 2 Decimal Place)</p>					

